

**STEEL CANOPY AT ECOMOMIC CENTER ,NARAHENPITA.**

**BOQ**

ITEM	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
<b>A</b>	<b>PRELIMINARIES</b>				
A1	Removing Existing Canopy	Item			
	<i>Following items are included to the rate</i>				
	Removing Existing ZN/Al Roofing sheets				
	Removing Existing panel ceiling & Fascia(Aluminium canopy side)				
	Removing Existing steel frame work				
	Removing Existing electrical line				
A2	Debries removing from site.	Item			
<b>B</b>	<b>STEEL STRUCTURE</b>				
B1	Supply ,fabricate & Fixing steel structure as per the detail drawing	Item			
B2	Supply & laying 4mm tk solid polycarbonate sheet,fixing self drilling screws.All join seall with fiber glass.	m2	65.00		
	<b><u>Structure Painting</u></b>				
B3	Apply with one coat of Etch primer,one coat of Marine paint (Petrokem or Egeler)& one coats of emulsion paint	Item			
<b>Total Amount</b>					-